INTERNSHIP · ELECTRICAL & SOLAR PV

Building electrical installations and a grid-tied PV plant

Ouerdani Electricity Corporation · Sousse · Jul – Aug 2026

14
PV modules of 570 Wc on a 3-row structure

NF C 15-100
standard behind the building installations

STEG / ANME
grid-connection framework

CONTEXT

Ouerdani is an ANME-accredited installer of building electrical systems and grid-connected solar plants. I followed real sites from survey to commissioning.

TOOLS AND METHODS

NF C 15-100 · Solar PV · Earthing · AC/DC protection · Technical drawings

WHAT I DID

- Wired and labelled distribution boards, installed lighting and socket circuits, and drew a board’s single-line diagram by hand.
- Sized breakers for air-conditioning circuits from the load, using $I = P / (\cos \varphi \times 230)$.
- Read the execution drawings and the structural calculation (Eurocodes, NV65 wind rules) of the PV structure.
- Fixed modules, made simple DC/AC connections and crimped lugs on the earthing bar, under technician supervision.

OUTCOME

Followed the project to the final check by the company’s technicians before commissioning, and learned how electrical work, structural design and administrative approval fit together on one site.

Wassim Farhat · Electrical & Automation Engineering
wassim.farhat@polytechnicien.tn